G. R. S. 59] GPB—15,000—22-7-14

GENERAL AND REVENUE SECRETARIAT.

1903. P8

(Municipal)

File No. /2/

Serial Nos. /–2

~~**Papers Filed.**~~ B

Month November 03

SUBJECT.

Construction of an octroi Katte at Davanagere

PREVIOUS REFERENCES. LATER REFERENCES.

Cwo' 1/12

Docketed : Kattabhinamiga

SECTION

FILE No.

From H. R. Ramanujacharya Esquire,
President Municipal Board
Chitaldrug District

To V. Krishnaiyangar Esquire
Secretary to the Government
of His Highness the Maharaja
of Mysore, Revenue and
General Departments
Bangalore

Dated 4th October 1903
Despatched
Received
General No. 183
No. Sec 4

Enclosure No. 3

7 OCT. 1903 L738

1903

Submitting for sanction an estimate in duplicate together with a plan amounting to Rs 2332/- for constructing an Octroi Katte or Warehouse at Davangere for taking in all piece-goods liable to Octroi duty as soon as they are imported into the town for consumption vice versa.

Draft submitted for appl
30/10/03

The Dewan through the 2nd Councillor

Rs 10 00

30/10

Sent A.

Sent to Accts Office 31/10/03

10/5

Office of the President of Municipalities
Chitaldrug District

No. 183 Encl
Sec 4. 3

Dated Chitaldrug, the 6th October 1923

From

H. Ramanujayengar Esquire
President of Municipalities
Chitaldrug District.

To

H. V. Nanjundayya Esquire, M.A. B.L.
Secretary to the Government of
His Highness the Maharaja of Mysore
General and Revenue Departments,
Bangalore

Sir,

I have the honor to submit herewith in duplicate an estimate amounting to Rs 2,332 for Constructing an Octroi Katte or Ware-house in Davanagere for taking in all piece-goods liable to octroi duty as soon as they are imported into the town for consumption for the purpose of being stamped and for storing such of those as are intended to be kept in the town for a time prior to their export to their places of consumption locally as occasions arise and kept in the possession of the Municipality for safe custody and to state that having

regard

regard to the commercial importance of the place, the Municipality is badly in need of a pakka building for the purpose above indicated and the members are very solicitous of its early construction on a suitable site At present, the goods are being stored in a private building hired for the purpose inside the town on a monthly rent of Rs 7 and this arrangement does not work satisfactorily I beg therefore that Government may be pleased to accord sanction to the estimate for the proposed ware-house. The Cost will be met from the sum of Rs 2450/- provided in the sanctioned budget for current year under the following sub-heads of Public Works

	Total sum	amount to be appropriated
XIII Public Works (b) Buildings Original	2300	2300
Do — (j) Road widening	150	32
	2450	

2. A plan of the above buildings is enclosed for reference and kind return

I have the honorable,

Sir,

Your most obedient Servant,

[signature]

for President

L. F. W.] Estimate of the Probable Cost of Constructing Office house at Daranagal

Detail of works	No.	Dimensions			Contents	Total.
Earth work Excavating foundation						
Front rear and Cross walls	3	30½	3	3	823	
Side Walls	2	29½	3	3	531	
" Step	1	13	3	1	39	
Filling in basement	1	32	16	1	512	
— Do — Verandah	1	32	8	1	256	
Total C.ft					2161	= 80 C.yds.
Filling foundation						
Concrete with ordinary Mortar						
Front rear and Cross walls	3	30½	3	½	137	
Side walls	2	30	3	½	90	
Retaining walls	3	8	3	½	36	
Pillars	4	3	3	½	18	
Total C.ft					281	= 281
Do Burnt Stone in Chunam						
Front and rear walls	2	31	2½	2½	387½	
Side walls	2	27	2½	2½	337½	
Retaining walls	3	9⅔	2½	2½	181	
Pillars	4	2½	2½	2½	62½	
Step	1	12½	3	1	37½	
Basement						
Front and rear walls	2	31½	2	1½	189	
Side walls	2	27	2	1½	162	
Retaining walls	3	9⅔	2	1½	87	
Pillars	4	2	2	1½	24	
Step	1	12	2	½	12	
Total C.ft					1480	1480
Superstructure Burnt brick in Chunam						
Front and rear walls	2	32	1½	16	1536	
Side walls of Hall	2	17	1½	16	912	
Side Walls of Verandah	2	8	1½	11½	276	
Gables of Hall	2	17½	1½	3	158	
" do of Verandah	2	9½	1½	3½	100	
Pillars	4	1½	1½	7	63	
Total C.ft					3045	

Deduct	Doorway	1	4	1½	7		
	Windows	7	3	1½	4	126	
	Total Deductions					168	
	Balance C. ft					2977	237
Boring with Cuddapah Slab							
	Hall	1	31½	15½	½	488	
	Verandah	1	31½	7½	½	236	
	Total Square					7·24	7·24
Plastering with morlar							
	Hall inside	1	96	.	16	4536	
	Verandah inside	1	48	.	7	336	
	Hall outside	1	73	.	16	1168	
	Verandah outside	2	8	.	11½	184	
	Pillars all round	4×4	1½	.	7	168	
	Gable of Hall	2×2	17½	.	3	210	
	— Do — of Verandah	2×2	9½	.	4½	171	
	Step both the Sides	1×2	1½	.	1½	23	
	Basement all round	1	127	.	1½	190	
	Total Square					3986	
	Deduct Doorway	1	4	.	7	28	
	Windows	7	3	.	4	84	
	Total deductions					112	
	Balance Square					38·74	38·74
White Washing							
	After plastering ceiling:					38·74	38·74
Roofing							
	Mangalore tiles and teak rafters	1	39	38	:	14·82	14·82
Wood Work							
Teak wood	Common rafters long	26	25½	3"	6"	83	
—	Do — Small	26	13½	3"	6"	44	
	Wall plates	2	38½	5"	6"	14	
	Breasummers	1	38	5"	7"	9	
	Collars	26	9	3"	6"	29	
	Total C ft					179	179
Teak door panelled		1	4	.	7	28	28 Sft
— Do — Windows pallisaded with 1" iron bars		7	3	.	4	84	84 Sft
Painting with Chocolate or green							
	Door both the Sides	1×2	4	.	7	56	
	Windows — Do —	7×2	3	.	4	168	
	Total Square					2·24	2·24
Cuttak Slabs dressed							
	Over Pillars	4	1½	1½	6"	9	
	Top and bottom of Door	1×2	5	1½	6"	15	
	over Windows	1×7	4	1½	6"	42	
	Total C ft					66	66

Abstract

6

Abstracct.

Items	Per	Rate,	Quantity	Amount
Earthwork	C yds	2 -	80	10
Concrete with ordinary mortar	Cft	2 -	231	35
Burnt Stone in Chunam	— Do —	2 6	1480	231
Burnt brick in Chunam	— Do —	3 -	2577	539
Flooring with Caddapa Slabs with 3" Concrete below	Sqr	32 - -	7·24	232
Plastering with mortar	— Do —	2 8 -	38·74	97
White washing	— Do —	- 3 -	38·74	7
Roofing with Allenflore tiles 1st class and teak reapers	— Do —	20 - -	1452	227
Teakwood work	Cft	3 8 -	179	626
Teakwood doors panelled	Sft	12 -	23	21
Teakwood windows panelled and with 1" iron bars	Sft	1 4 -	84	105
Painting	Sqr	3 - -	2·24	7
Burnt Stone slabs dressed	Sft	6 -	66	25
Total Rupees				2222
Add Contingencies at 5 Percent				110
Grand Total Rupees	-	-	-	2332

Rupees two thousand three hundred and thirty two only

Abdulkareem

for President of Municipality
Cuddalore Municipality

1/64

7

Proceedings of the Governors
Council
of H. M. the Maharaja of
Nepaul

SECTION
FILE NO. 12 of 3

Read.

Letter no 183 dated the 6th October 1903, from the President of the Municipality to the Chief Secretary which submitting one Solution (in duplicate) and plan showing G.O. 2332 for Constructing an Octroi Katta or Ware-house on Davenport for storing all kinds goods liable to Octroi duty, when they are unpacked into the town for Consumption &c

Order Recommended

Sanction is accorded to the Solution received with the above,

Applied - I know the date selected & I think this a good one - Do the Calcutta Municipality proposed by the Secretary have no objection thereto? If after omitting it -

30/10/03

Hm
30/10
13738
2.41.03

1747-S
L. 161-02 31/10/03

Encl: 1 Plan
1 Resolution
& Copy of letter to Secretary to Govt.

the charge hereof made from the unexpirable notes provisions made in the current year budget of Bassingere under the head VIII, Public Works. The building should be located in a place ~~easy to guard~~ which can be easily guarded without add- cost.

		Provisions	Approved
Buildings original.	£	2300	230
Roads isolating.	£	150.	32
Total.			2332

29/10/03

Sd/- 31/10/03

To The Provincial Commissioner, Mechi Zonal, Jhapa, with Estimate & Plans

5/11/03

The Commissioner of the Eastern Region with Copy of the abstract Estimate

3.XI.03

N